

1 Novel FRF-based fast modal testing of multi-storey
2 CLT building in operation using wirelessly synchronised
3 data loggers

4 Wai Kei Ao^{a,*}, Aleksandar Pavic^{b,**}, Blaž Kurent^c, Fernando Perez^d,

5 ^a*The Hong Kong Polytechnic University, Civil and Environmental Engineering, Hung
6 Hom, Kowloon, Hong Kong*

7 ^b*University of Exeter, Vibration Engineering Section, College of Engineering,
8 Mathematics and Physical Sciences, North Park Road, Exeter EX4 4QF, U.K.*

9 ^c*University of Ljubljana, Faculty of Civil and Geodetic Engineering, Jamova cesta 2,
10 1001 Ljubljana*

11 ^d*Smith and Wallwork Ltd, 50 St Andrews Street Cambridge, CB2 3AH, UK*

12 **Abstract**

13 This paper presents a novel input-output frequency-response function
14 (FRF) based field modal testing (MT) of an operational and fully occupied
15 tallest cross-laminated timber (CLT) building in the U.K. A custom-built
16 MT system and testing protocol were developed to facilitate exceptionally
17 fast field testing work lasting only 10 h, including all instrumentation and
18 field testing work.

19 This yielded eight fundamental and higher-order modes of vibration with
20 natural frequencies up to 12 Hz. The higher order modes are normally not
21 possible to measure well enough using the standard output-only operational
22 modal analysis (OMA). An FE model was developed prior to the testing to
23 assure quality and facilitate the fast testing process. The FE model, based
24 on the best engineering judgement, proved to be able to predict very well the
25 key features of the test building. This includes close matching and correct
26 clustering of the FE-calculated and MT-estimated natural frequencies, as
27 well as a very reasonable prediction of the static stiffness at the top of the
28 building. The in-situ measured horizontal static stiffness at the top of the
29 CLT building is a considerable benefit of the field FRF measurements and
30 is not possible in the standard OMA. It was shown that the preliminary
31 best practice FE model was over-predicting the static stiffness in the two
32 orthogonal directions by only up to 22 % of the measured values.

*Corresponding author
Principal corresponding author
Preprint submitted to *Mechanical Systems and Signal Processing* 6th January 2023
Email addresses: waikei.ao@polyu.edu.hk (Wai Kei Ao), a.pavic@exeter.ac.uk
(Aleksandar Pavic), blaz.kurent@fgg.uni-lj.si (Blaž Kurent),
fernando.perez@smithandwallwork.com (Fernando Perez)

33 Curve-fitting of the good quality FRF data yielded damping ratio values
34 for the higher order modes of vibration, typically above 3 %. This is quite
35 high for a full-scale multi-storey residential building.

36 *Keywords:*

37 modal testing, full-scale, CLT building, frequency response function,
38 OCXO-based synchronised data loggers

39 1. Introduction

40 Medium to very tall high-rise buildings dominate the skylines of many
41 cities in the world, which decided to go 'up' rather than 'out' to cope with
42 transportation and other challenges facing their growing population. Vibra-
43 tion serviceability due to wind-induced lateral sway has become the de-facto
44 governing design criterion for high-rise buildings above 50 m, dictating the
45 size, shape and therefore cost of such structures [1]. Damping ratios and
46 natural frequencies of all modes of vibration that can be excited by wind are
47 the key modal parameters which are used in design to size the structure and
48 predict wind-induced sway vibrations of tall buildings in service.

49 However, long-term practice is showing that damping and natural fre-
50 quencies of tall buildings are also quite unreliable parameters to assume in
51 design. Underestimation of the fundamental natural frequency of up to 50 %
52 by the finite element model (FEM) relative to its experimental counterpart
53 is common ([2]). The situation with damping ratios is similar or worse due
54 to even greater uncertainties in the values of modal damping ratios measured
55 in as-built buildings. This is because the natural frequencies and damping
56 ratios in as-built tall building structures are fundamentally non-linear and
57 amplitude-dependent ([2]). Therefore, standard output-only ambient vibra-
58 tion testing (AVT), also known as ambient vibration survey (AVS) or opera-
59 tional modal analysis (OMA), methods for their estimation - based only on
60 the measured responses to unmeasured ambient excitation which vary with
61 time - are naturally producing estimates of modal parameters which vary
62 considerably from one block of data to another ([3]; [4]).

63 An input-output modal testing (MT), or experimental modal analysis
64 (EMA), where both the excitation force and the corresponding dynamic
65 response are measured simultaneously with the aim of experimentally es-
66 timating the structure's frequency response function (FRF) is a much more
67 powerful tool to deal with structural non-linearities and uncertain modal

68 parameters such as the natural frequency and damping. For decades MT has
69 traditionally dominated aerospace and automotive sectors, whereas AVT has
70 been very much used in experimental dynamic testing of large civil engin-
71 eering structures. This even though AVT has, by its very nature and due to
72 its underpinning assumptions ([5]; [4]), rather inferior performance as to its
73 quality of modal parameters relative to MT.

74 The key reason for this situation is practical difficulties in exciting a
75 massive full-scale tall building in a noisy open-space environment with a
76 measurable force causing measurable response without damaging the building
77 at the point of excitation. Even if this first problem is, overcome then the
78 next is the logistical challenge of measuring such responses simultaneously
79 throughout the building. These are needed to estimate experimentally mode
80 shapes to complete the set of four modal properties: natural frequencies,
81 modal damping ratios, modal masses, and mode shapes. Finally, the last
82 problem is to do it extremely fast on a typically operational building, which
83 is relevant and needed for serviceability investigations, to avoid disruption.
84 Hence, MT results based on the experimentally measured FRFs across a wide
85 range of frequencies, fast and in operational multi-storey buildings practically
86 do not exist in the literature.

87 This paper addresses this gap and describes a novel FRF-based MT of a
88 multi-storey residential building in operation to measure its important sway
89 modes. The building is the tallest timber building in the UK constructed
90 in 2017 in Glasgow in an area known as Yoker. The Yoker building is a
91 seven-storey building containing 42 occupied flats made entirely of cross-
92 laminated timber panels. To the best knowledge of the authors, this is the
93 first ever attempt to conduct an FRF-based MT on an occupied multi-storey
94 residential building.

95 The testing was conducted using a set of synchronously operating elec-
96 trodynamic shakers and wirelessly synchronised oven-controlled crystal os-
97 cillator (OCXO)-based data logger in conjunction with high-precision accel-
98 erometers for simultaneous force and response measurements ([6]). The key
99 novelty of this MT system is that it makes no use of cables or radio waves to
100 connect the response accelerometers throughout the building simultaneously
101 with the multi-channel data acquisition system. However, it still provides a
102 perfect synchronous measurement of a practically unlimited number of force
103 and response channels. This new FRF-based modal testing process will be
104 described in detail in this paper using the Yoker building as a case study.

105 After the introduction, Section 2 describes the test structure. Section

106 3 presents finite element (FE) modelling and results of the modal analysis.
107 Following best practice in FRF-based modal testing ([7]), these preliminary
108 results informed the set up of the modal testing apparatus and the cor-
109 responding testing protocol, which are presented in Section 4. Section 5
110 describes the results of the modal testing and compares them with the pre-
111 liminary FE modelling results. Finally, Section 7 presents conclusions.

112 2. Structural description

113 Figure 1 is two photos of the Yoker building made in November 2019.



Figure 1: Two views of the Yoker building.

114 The main load-bearing super-structure of the building is made entirely of
115 CLT panels: horizontal for floors and vertical for the internal walls, including
116 the lift shaft and façade. Only the foundations and ground slab are made of
117 reinforced concrete, as appropriate.

118 The building has a T-shaped plan and is divided into North and South
119 wings, as shown in Figure 2. The North wing is connected to the Southern
120 wing only through the communal corridor/lobby where the stairwell and lift
121 are located. The lightweight cladding was used for the façade. The height
122 of the building is approximately 22 m. Figure 3 shows key structural details
123 and CLT connections of the Yoker building.

124 The total mass of the building is approximately 1,300 tonnes.

125 3. FE modelling in preparation for modal testing

126 Following good practice and to quality assure full-scale modal testing, a
127 representative finite element (FE) model was developed ([7]) based on the
128 best engineering judgement using ANSYS software ([8]).




Figure 2: Isometric, side and plan views of the Yoker building.




Figure 3: Key structural details of the Yoker CLT building (after [8]).

129 The CLT panels were modelled using the SHELL181 ANSYS element, and
 130 these elements accounted for 515 t of the total mass of the building. Then,
 131 the mass of well-defined non-structural elements (partitions, etc.) was 685 t,
 132 and the 'uncertain' mass of other non-structural elements, such as furniture,
 133 doors, windows and services, was estimated at 70 t. The non-structural mass
 134 was distributed throughout the building based on its location by increasing
 135 the mass of the relevant structural elements, as appropriate, using SURF154
 136 elements. Five types of CLT panels were used with three or five layers with
 137 total thickness varying from 100 to 200 mm. Key material properties of
 138 timber were assumed based on the data from its producer Stora Enso ([9]),
 139 as follows:

- 140 • Elastic moduli $E_0 = 12,000$ MPa and $E_{90} = 370$ MPa;
- 141 • Shear moduli: $G_{0,90} = 460$ MPa and $G_{90,90} = 50$ MPa;
- 142 • CLT density: $\rho = 470$ kg/m³;
- 143 • Poisson's ratio is $\nu_{0,90} = 0.3$

144 The ₀ and ₉₀ sub-scripts represent the timber layer's orientation angle
 145 in the CLT panel. The wall-to-wall and wall-to-floor CLT connections were
 146 assumed to be rigid. Further details of this initial FE model are presented
 147 elsewhere ([8]).

148 Figure 4 shows the considerable level of the FE modelling detail and the
149 meshing size adopted.




Figure 4: The Yoker building FE model and its meshing detail.

150 Figure 5 shows the eleven FE-calculated modes of vibration, which were
151 used to inform the modal testing. There are two clear clusters: around 3-4 Hz
152 and 8-12 Hz. This kind of clustering is therefore expected to be observed in
153 the experimental FRF data during their initial in-situ quality check.

154 4. FRF-based modal testing of occupied full-scale building

155 As previously mentioned, FRF-based modal testing of an occupied multi-
156 storey residential building is an ultimate challenge in vibration serviceability
157 research on fully operational buildings. Being input-output based, it provides
158 the best quality experimental modal data (natural frequencies, mode shapes,
159 modal damping, modal mass) for a fully operational residential building.
160 As opposed to partially finished buildings, which are normally available for
161 and used for AVT in the past, modal data from occupied residential build-
162 ings based on experimental FRFs over a full range 0-12 Hz is virtually non-
163 existing.

164 4.1. Modal testing and FRF data acquisition specifications

165 The key reason for this situation is the tremendous practical and logistical
166 problems to:

- 167 1. gain access to an occupied building and carry out the tests quickly and
168 without disturbing the building occupants,




Figure 5: Natural frequencies and mode shapes of the first 11 modes of the Yoker building.

- 169 2. provide and operate sufficient measurable excitation, typically at the
170 top of the building, and
- 171 3. record continuously and simultaneously the excitation force and the
172 corresponding vibration response at multiple levels of the building,
173 which is needed to measure the mode shapes.

174 Therefore, the following specifications were developed for this modal test-
175 ing:

- 176 • To address problem 1, the testing had to be finished in a single day
177 using only existing facilities within the building (staircases, an elevator,
178 normal mains 240 V power supply, single parking space in front of the
179 building, etc.).
- 180 • To address problem 2, a set of portable horizontal shakers was em-
181 ployed, which could be moved manually and transported to the top of
182 the building using the existing elevator in the building. The shakers
183 were selected based on the FE calculated natural frequencies and modal
184 masses calculated using a unity-scaled mode shapes (Figure 5) so that
185 they had sufficient force to excite the whole 1300-tonne building lat-
186 erally. This was done in conjunction with the ultra-sensitive accelero-
187 meters distributed throughout the building, which could measure the
188 resulting building sway response.
- 189 • To address problem 3, there was a need to eliminate wires between the
190 accelerometers throughout the building and the multi-channel force
191 and response data acquisition system at the top of the building, placed
192 next to the exciters. Therefore, a novel wireless data acquisition system
193 was developed able to simultaneously record multi-channel force and
194 acceleration digital data in the time domain. Considering that radio
195 connections seldom work well in occupied buildings, a set of very pre-
196 cisely synchronised data loggers was developed. This was based on an
197 oven-controlled crystal oscillator (OCXO) synchronisation enabling less
198 than a micro-second time shift between the physical loggers, which was
199 more than enough accuracy for FRF measurements of a low-frequency
200 civil engineering structure. Figure 6 shows the hardware of the OXCO-
201 based data logger. This device, developed in the laboratory of the
202 Vibration Engineering Section (VES) at the University of Exeter is
203 described in detail elsewhere ([10]; [6]).

204 OCXO-based data loggers could distinguish between 'master' and 'slave'
205 during application. As a master clock/ticks, only one distributed data
206 logger is initially chosen. The chosen 'master' data logger must then be
207 connected to the DC/AC power in order to activate. A beep sound is
208 announced when the master data logger and clock/ticks are successfully
209 activated. The remaining 'slave' data loggers and the local clock/ticks
210 are then separately powered on and activated using the same procedure.
211 The next step is to synchronise the 'local' units. The correlated graphi-
212 cal block diagram programming of Labview is demonstrated in Figure
213 7a. The primary concept is to convert the binary 'master' clock ticks
214 into an analogue number and subtract the 'slave' clock to calculate the
215 difference. Then, the 'master' clock/ticks could be added/overwritten
216 the difference to other 'slave' clock/ticks. This action is physically done
217 using a BNC cable to connect the 'master' data logger output port with
218 each of the 'slave' units' input port, as shown in Figure 7b.

219 The OCXO-based data logger also includes on-site visualised data re-
220 cording and time synchronisation operations, as shown in Figure 8. A
221 'master' clock/ticks (see Figure 8a) was counting the number beyond
222 the others. Figure 8b shows one of the slave clocks/ticks. It can be
223 seen that the 'slave' OXCO count/ticks was lower than the 'master'
224 OXCO count/ticks since the first 300000 sample points were recorded
225 before the 'master' OCXO added or overwrote any ticks. After that,
226 the physical BNC link from the 'master' to the 'slave' clock/ticks, the
227 'slave' unit could be overwritten at the precise synchronised point, re-
228 sulting in an OCXO count jumping, as shown in Figure 8b insert plot.
229 This jumping might serve as a time synchronisation indicator, making
230 it convenience for the test crews to observe the time synchronisation
231 process in real-time. The benefit only took a few seconds for each 'slave'
232 unit and was conducted once at the start of the test.

233 *4.2. Modal testing test grid throughout building*

234 To avoid disturbing the building occupants, the key instrumentations
235 (shakers and accelerometers) were placed only in the building corridor(s) as
236 no permission was given to enter and instrument any of the 6 flats on each
237 floor level. Therefore, there are no test locations at the far ends of the North
238 and South wings of the building, which would be logical choices to pick up
239 more twisting modes (Figure 2). Figure 9 shows the modal testing grid and






Figure 6: OXCO-based data logger featuring CompactRIO data acquisition hardware (after [10];[6]).




(a) LabVIEW real time block diagram of the CompactRIO-9064




(b) Time synchronisation: connecting a 'master' OCXO to 'local' OCXO units

Figure 7: Master and slave OCXO units time synchronisation (after [6]).



(a) Master OCXO



(b) Slave OCXO

Figure 8: Demonstration of 'master' clock/ticks OCXO count adding/overwriting the 'slave' clock/ticks to achieve the time synchronisation process.

240 orientation of accelerometers adopted over the height of the building. Figure
 241 10 shows the measurement points and locations on the plan of the typical
 242 floor levels.




Figure 9: Test grid points were possible only within a rectangular corridor between the six flats shown in Figure 10.

243 Clearly, with such a limited test grid, a potential issue could have been
 244 with an insufficient spatial resolution to describe the mode shapes sufficiently
 245 well. To check this, an auto Modal Assurance Criterion (Auto-MAC) [7] was
 246 calculated using the selected test points and degrees of freedom (DOF) in the
 247 FE-calculated mode shapes (Figure 11). The limited test grid, in principle,
 248 has sufficient resolution to describe the eleven identified modes of vibration
 249 (see parts of the mode shapes corresponding just to corridors in Figure 5).
 250 The only exception is modes 2 and 4, which could be swapped and misinter-
 251 preted due to their high AutoMAC value of 0.8. Figure 12a shows a setup
 252 for the FRF point mobility measurement at the top floor and Figure 12b
 253 shows a typical response-only setup at one of the lower levels in the building.
 254 It is noted that Figure 13 demonstrates the horizontal alignment and setup
 255 details for several shakers. The self-weight plus reaction mass and friction-
 256 grasping support frame may successfully stabilise the shaker. Additionally,
 257 the proper input force management is required to guarantee that the driving




Figure 10: Modal testing instrumentation shown in floor plans.

258 voltage results in steady shaker operation. After that, the shaker will not
 259 be requested to add any extra consolidated mounting. This semi-mounted
 260 method could be less disruptive, less intrusive, and flexible to the occupied
 261 properties, such that there is no need to request new drilling holes and use an
 262 invasive mounting strategy. This is another crucial justification for adopting
 263 these settings. The input voltage trail (from 0.5 to 1.75 V) for testing the
 264 ideal input voltage to drive the shaker is shown in Figure 14. The finalised in-
 265 put voltage was chosen at 1.5 V to compromise functionality and safety after
 266 on-site visualisation of the shaker stroke, force output level, robustness, and
 267 structure-shaker connecting stability. Consequently, the shaker and structure
 268 did not require any special connections or stingers.

269 4.3. Modal testing data flow

270 A key limitation of the OXCO-based data loggers is that they could not
 271 be live-monitored during the modal testing. Although they recorded simultane-
 272 ously all the time-domain modal testing data, that was done 'blindly'
 273 during the testing as the recorded data were available for visualisation and
 274 post-processing only after the testing.

275 However, a good practice in MT ([7]) and a key part of the quality as-
 276 surance system in VES when doing FRF-based field modal testing is to -
 277 at least - visually monitor the formation of the point-accelarance FRF. This
 278 FRF is crucial for the curve-fitting quality ([7]). In noisy, open-space envir-
 279 onments experimental measurement of FRFs requires averaging of multiple
 280 data blocks to remove extraneous noise on response channels ([7]). Greater






Figure 11: AutoMAC calculation corresponding to first 11 modes of vibration based on the pre-test FE model.



(a) Excitation and response measurement setup at top floor



(b) Typical response-only point measurement setup

Figure 12: Modal testing instrumentation featuring OXCXO-based data loggers: (a) measurement of the excitation using three APS400 electrodynamic shakers (the photo shows only two shakers) by utilising QA 750 sensors mounted on the shakers to measure the acceleration of the moving shaker armature of known mass and on the floor to measure floor accelerations; (b) typical QA 750 sensors setup to measure floor horizontal accelerations on one of the lower floor levels.




Figure 13: The configuration detail of the APS shaker horizontal setup and friction-grasp mount in the laboratory and field testing.




Figure 14: Different trail input voltage evaluation for the shaker.

281 extraneous excitation (e.g. due to wind) requires more averages to remove
282 it and hence longer data acquisition. Therefore, the number of averages de-
283 pends on the level of that extraneous noise which is never known in advance
284 of the test. By live monitoring how the point-acceleration FRF 'settles' and
285 stabilises with the increasing number of averages, the overall data acquisi-
286 tion time can be set. This is of crucial importance in severely time-limited
287 exercises of this type whereby a minimum number of averages is needed to
288 shorten the data acquisition time while still producing a usable set of FRFs.
289 Figure 15 shows a point acceleration FRF measured on the Yoker building
290 after only 1 average using 80 s of data and after 100 averages using over 30
291 minutes of data with 75 % of data block overlapping. The difference between
292 them is remarkable, indicating the importance of the monitoring of the FRF
293 formation during the MT.


294 To address this quality assurance problem, a standard 'wired' spectrum
295 analyser (SA) was used to monitor only the formation of the point-acceleration
296 FRF corresponding to the shaker excitation and structural response at the
297 top of the building. This was done using a separate and independent set
298 of 'wired' transducers measuring nominally identical data as the transducers
299 feeding data to the OXCO data logger. These wired transducers were posi-
300 tioned very close to the data acquisition centre to reduce the length of the
301 standard wires, as shown in Figure 16. The spectrum analyser was also used
302 to generate random signals for the shakers.

303 Figure 17 shows the data flow enabling 'dual' measurement of the point
304 mobility FRF for on-site immediate visual inspection and off-site post-processing.


305 *4.4. Modal testing instrumentation*

306 Apart from the already described OXCO-based data logger (Figure 6),
307 the spectrum analyser used was the 20-channel Data Physics DP730 in con-
308 junction with a 10-channel signal conditioner (Figure 18a) for Honeywell
309 QA 750 uniaxial force-balanced accelerometers ([12]). Also, Japan Aviation
310 Electronics (JAE) JA-70SA tri-axial MEM accelerometers ([13]) were used
311 to measure the structural response. The two types of accelerometers used
312 are shown in Figure 18b.

313 Figure 18a also shows a compact and portable instrumentation rack fea-
314 turing amplifiers for the three APS shakers used as well as the laptops for
315 driving the system and immediate point acceleration FRF data (instantan-
316 eously available from the spectrum analyser) processing, part of the VES
317 QA system for field FRF measurements. Namely, considering very short



(a) Point acceleration FRF measurement



(b) Point acceleration FRF measurement

Figure 15: Point acceleration FRF measurement in the North-South (X-direction, Figure 9) at 6th floor. (a) corresponds to one averages, and (b) corresponded to 100 averages which is the final number of averages adopted for the measurements. Total data acquisition time to be able to do 100 averages with 75 % overlapping and Hanning windowing of data blocks was over 1800 s.




Figure 16: Dual 'wired' and 'wireless' FRF data acquisition system at the top of the building. It can be seen that the shakers have two accelerometers each mounted to measure the same acceleration of the moving armature of the known mass i.e., the excitation force. For each shaker, signal from one accelerometer is wired directly into the spectrum analyser (green lines) while the other accelerometer is connected to the yellow OCXO box (red line). The two accelerometers measure nominally the same acceleration.




Figure 17: Flow of data in the 'dual' wired and wireless FRF data acquisition system (after [11])

318 time scales to run the tests and often inability to repeat the test at a later
 319 date if something goes wrong and is not discovered immediately, part of the
 320 QA process used requires immediate processing of any of the in-situ avail-
 321 able FRFs to check if they could be processible producing meaningful modal
 322 estimation. Further information on the adopted instrumentation and meth-
 323 odology used is available elsewhere ([6]).




Figure 18: (a) Data acquisition centre and (b) Uniaxial QA 750 and tri-axial JA-70SA accelerometers used and their alignment in the X and Y directions of the CLT floor of the Yoker building.

324 4.5. Modal testing logistics and timing

325 After six months of preparations and practising fast deployment, setting
 326 up, data acquisition, checking and packing of the modal testing equipment,
 327 the FRF-based modal testing took place on 21st, January 2020. The test
 328 team had four members, and the whole of the test equipment was packed
 329 in a single van occupying only a single car park space at the Yoker building
 330 (Figure 19). The modal testing was done in only 10 hours. The test team
 331 arrived at 8 a.m., unloaded and deployed the equipment, performed modal
 332 testing, packed and loaded the equipment back into the van. The team left
 333 the site by 6 p.m. on the same day.

334 4.6. Modal testing raw data and their checks

335 As the speed of the modal testing process was of paramount importance,
 336 a broadband random excitation 0-12 Hz was applied through three synchron-



Figure 19: A long wheelbase van with equipment packed and ready to be deployed. The total weight of the equipment was less than 1 tonne and individual pieces were less than 50 kg each enabling safe and easy manual handling by two people.

337 ously running shakers, first in the X-direction (Figure 20a) and then in the
 338 Y-direction (Figure 20b). This was done via a random signal generated by
 339 the DP730 spectrum analyser which was simply split three ways so that
 340 three identical analogue random signals were fed to the amplifiers of the
 341 three shakers generating their driving voltage.




Figure 20: Synchronous random excitation by three horizontal APS400 shakers: (a) in the X-direction and (b) in the Y-direction.

342 4.6.1. Checking of synchronously running shakers

343 Multiple shakers had to be utilised in the test to provide a sufficient force
 344 level to excite the structure. The BNC channel T-splitter (see Figure 21)
 345 could be used at the spectrum analyser output port to diversify the input
 346 signal and drive each exciter to reach the performance of the single input,
 347 which could ensure the exciters were operating in phase. In other words, when
 348 the shakers receive out-of-phase input, they behave non-synchronised, which

349 results in a time delay and amplitude deduction issues that lower the total
350 force generation. The synchronised sinusoidal input time history evidence
351 of shakers is shown in Figure 22. Each shaker input force measurement's
352 forms under various resonant sinusoidal excitation frequencies had a constant
353 amplitude and phase. The total force engagement was taking the sum of the
354 shakers instead of averaging the value.





Figure 21: Spectrum analyser and BNC channel T-splitter of the single output port.


355 4.6.2. Excitation in X-direction

356 A single-input multiple-output (SIMO) FRF measurement and modal
357 testing process was applied, with all three shakers assumed to generate a
358 single random force exciting the building at its top and along a single de-
359 gree of freedom (DOF) corresponding to the location and orientation of the
360 shakers at TP1 (Figure 9). Although the shakers excited only one DOF
361 (either X- or Y- direction) at the time, the structural vibration responses
362 were measured in both X- and Y- directions simultaneously over all floor
363 levels. This resulted in a single column of the FRF matrix with a total of 26
364 elements, half of which corresponding to the X-direction and the remaining
365 half to the Y-direction excitation at TP1 (Figure 9).

366 As previously mentioned, the shaker force was measured by measuring
367 acceleration (using QA 750 accelerometers) of the shaker armature mass of
368 22.95 kg. Hence, Figure 23a shows the total force applied at TP1 in the
369 X-direction and the corresponding acceleration responses in the X- direction
370 (Figure 23b) and Y-direction (Figure 23c). The root mean square (RMS)
371 of the random force signal was 500 N with occasional peaks just over 1 kN.
372 As the random vibrations caused by the shakers were not perceptible by the
373 test personnel at the top of the building or anywhere else within the building,



(a) Mode 1: $f_1 = 2.84$ Hz




(b) Mode 2: $f_2 = 2.93$ Hz

Figure 22: Input force time history of each shaker representing to modes 1 and 2.


374 it was reassuring to see that the random accelerations in the X-direction at
 375 TP1 were considerably larger than in the Y-direction, as expected consider-
 376 ing the mode shapes (Figure 5). This check was important to ascertain that
 377 the whole 1,300-tonne building was clearly responding to the shaker excita-
 378 tion in the X-direction in a logical manner in addition to any not measured
 379 extraneous excitation within and outside the building.

380 Using a 75 % overlap of individual data blocks lasting 80 s each, 100 av-
 381 erages, Hanning window were used to estimate the FRFs with the frequency
 382 resolution of 0.0125 Hz.


383 Based on these data acquisition and analysis parameters, Figure 15b
 384 shows FRF point accelerance in the X-direction at TP1 and Figure 24 shows
 385 FRF transfer accelerance between the X- and Y- directions at TP1. The
 386 transfer FRF magnitude has a considerably lower magnitude than the point
 387 FRF magnitudes, as expected, and it is also noisier due to worse signal-
 388 to-noise ratios. However, clear modes between 2 and 3 Hz are identifiably
 389 confirmed by clear phase shifts. After the modal test on the day, MATLAB
 390 was used to process data from the OXCO data loggers and the FRF plots in



(a) Total random force in the X-direction



(b) Acceleration response in the X-direction



(c) Acceleration response in the Y-direction

Figure 23: (a) Total random excitation force in the X-direction applied by three APS400 shakers applied at TP1. The corresponding random response at TP1 in (b) the X-direction and (c) the Y-direction.

391 Figures 15 and 24 also demonstrate that the 'wireless' OXCXO- and 'wired'
 392 SA-based data acquisition systems generate practically identical FRF data.
 393 This confirmed the ability of the OXCXO-based system to generate good-
 394 quality FRF data.




Figure 24: FRF transfer accelerance at TP1 between the excitation in the X-direction and response in the Y-direction (a) magnitude and (b) phase calculated by the spectrum analyser immediately (blue dashed line) and after return from the testing using OXCXO data (green line). The FRF data quality is good and the two sets of SA- and OXCXO-based FRF data are practically identical indicating the ability of the OXCXO-based data acquisition system to reproduce high fidelity FRF data identical to the standard, tried and tested spectrum analyser system.

395 4.6.3. Excitation in Y-direction

396 After acquiring and quality-assuring raw data in the X-direction, the
 397 shakers were rotated by 90 degrees to excite the building in the Y-direction,
 398 see Figure 20b. A testing process identical to the X-direction was followed
 399 and similar good quality of FRF data were obtained. To support that, Fig-

400 ure 25a shows FRF point accelerances for the X- and Y-directions at TP1.
 401 They indicate that the X- and Y-direction excitations resulted in a logical
 402 complementary set of point accelerance FRFs demonstrating that the lowest
 403 modes of vibration have components in both orthogonal directions as expected
 404 considering the FE-calculated mode shapes (Figure 5). Figure 25b shows
 405 that the two FRF transfer accelerances between X and Y DOFs at TP1 look
 406 nominally identical, indicating a successful FRF reciprocity check ([7]).




Figure 25: Comparison of FRFs at TP1 for shaker excitations in the X- and Y-directions. (a) are point accelerances. (b) are transfer accelerances between DOFs in X and Y directions at TP1.

407 4.6.4. Coherence function

408 The coherence function is defined as the relationship between input and
 409 output signals. Two highly correlated signals have an ideal linear constant
 410 parameter proportion when the coherence function is equal to one. The
 411 quality of the FRF-based measurement and the presence of noise can both be
 412 evaluated using the coherence function as an indicator. The noise could enter
 413 the measurement if the coherence function is less than one but greater than
 414 zero, which refers to the non-linear proportion between the input and output
 415 signals. Alternatively, the output signal could be caused by the original
 416 and other inputs. If the coherence is zero, the input and output signals
 417 are completely independent of one another. Figure 26 shows the coherence
 418 function for X- and Y-directions at TP1. The clustering frequency ranges
 419 of 2-4 Hz, 5.5-6.5 Hz, and 7-12 Hz have coherence values that are almost
 420 close to 1 with strongly correlated input-output signals and have a tolerable

421 amount of noise for the presentation of these modes. The range of 0-2 Hz
 422 and 4-5 Hz has a low coherence value due to uncorrelated relationships or no
 423 mode happened.




Figure 26: Coherence function of input output signal at TP1 for shaker excitations in the X- and Y-directions. (a) X and Y responses related to X-direction excitation. (b) X and Y responses related to Y-direction excitation.

424 4.6.5. Static stiffness check

425 By integrating twice the two measured FRF point accelerances, their
 426 corresponding FRF point receptances can be calculated ([14]). Figure 27
 427 shows that the excellent quality of the FRF data enables an estimation of
 428 the static stiffness at TP1 using the horizontal part of point receptance FRF
 429 modulus plot before the rise of the curve towards the first resonant peak.
 430 The experimentally estimated static stiffnesses are: $k_{TP1,X,EXP} = 143$ MN/m
 431 and $k_{TP1,Y,EXP} = 123$ MN/m. These compare well with their counterparts
 432 for the pre-test FE model with values readily available during the testing:
 433 $k_{TP1,X,FE} = 170$ MN/m and $k_{TP1,Y,FE} = 150$ MN/m, indicating that the FE
 434 model is up to 22 % stiffer than the test structure at TP1. The right order
 435 of magnitude and a relatively small error further increased confidence in the
 436 test data.

437 This was a last quality assurance check indicating good FRF data despite
 438 the large size and normal operation (generating plenty of the extraneous
 439 noise) of the as-built structure.





Figure 27: FRF point receptances for TP1 in the (a) X-direction and (b) Y-direction.

440 5. Modal testing results


441 5.1. Modal analysis

442 After the return to base, MATLAB code was used to process all of the
 443 data acquired using the OXCO-synchronised boxes yielding two columns of
 444 the FRF matrix measured. Therefore, it was possible to perform a multi-
 445 input multi-output (MIMO) curve-fitting procedure in which all FRFs are
 446 curve-fitted simultaneously ([14]). The multi-reference curve-fitting was done
 447 in the MEScope software [15] using the Complex Mode Indicator Function
 448 (CMIF) algorithm and two reference FRFs at TP1, corresponding to the
 449 DOFs in the X- and Y- directions, respectively. The good quality of the
 450 curve-fitting is demonstrated in Figure 28 with a clear indication that the
 451 two key point accelerance FRFs are well curve-fitted.

452 Finally, Figure 29 shows the estimated modal properties of this building.
 453 Despite the limited test grid, the modal properties in Figure 29 are logical and
 454 of exceptionally good quality. There are two clear clusters of modes: around
 455 3-4 Hz and 7-12 Hz. As previously mentioned, by visual inspection of the
 456 FE-calculated modes, similar clustering of modes is also presented in the FE
 457 modelling (Figure 5). This observation further enhances confidence in the
 458 FRF-based modal testing results. Figure 30 also compares the experimental
 459 and FE models' natural frequencies, MAC values, and mode shapes before
 460 and after model updating. Again, the updated model's result obtained an
 461 acceptable match to the measurement. More specific information about the
 462 model updating may be found in the author's previous paper [8].



(a) Curve-fitting of moduli of all 52 FRFs



(b) Curve-fitting of moduli of two FRF point accelerances

Figure 28: Results of MIMO multi-reference curve-fitting with the estimated model represented by a dashed red trace plotted over the 52 (2×26) measured FRF moduli.




Figure 29: Estimated experimental modal properties using multi-reference FRF curve-fitting.




Figure 30: Graphical comparison of initial and updated model with experimental data (after [8]).

463 5.2. Evaluation of potential excitation level

464 Figure 31 shows the FRF magnitude plot driving in current and voltage
 465 modes of one APS shaker. The current drive at 1.5 Hz exhibited a clear
 466 resonant with a prominent peak. After 2 Hz, the platform may be steady
 467 with a constant output, but the voltage drive would not experience this
 468 kind of peak overshoot. Therefore, the voltage drive was selected in this
 469 horizontal excitation setup. Random excitation was used for the first test in
 470 the modal testing, with a driving voltage of 2 V per shaker. The first mode
 471 of the structure is 2.85 Hz, burying into the shaker’s steady output dynamic
 472 frequency range. This might ensure that the shaker’s driving force will be
 473 sufficient to excite the structure to the right level.




Figure 31: FRF magnitude plot of APS shaker driving in current and voltage modes.

474 Figure 32 shows a single APS shaker’s excitation force time history, which
 475 had an amplitude of about 165 N root mean square (RMS). Otherwise, Figure
 476 23a depicts the total excitation force, with an RMS amplitude of about 500 N
 477 needed to excite a 1300 tonne timber building.

478 A technical report from concrete society suggested the response calcula-
 479 tion of low-frequency floor [16], the steady-state acceleration response at a
 480 position i in a single mode n of frequency f_n at a given excitation frequency
 481 hf_p can be calculated as follows:

$$a_{i,n}(hf_p) = \mu_{i,n}\mu_{j,n} \left(\frac{hf_p}{f_n} \right)^2 \frac{P_{j,h}}{M_n} \text{DMF} \quad (1)$$

482 where hf_p is the harmonic excitation frequency. The harmonic excitation
 483 force of amplitude $P_{j,h}$ is applied at location j . $\mu_{j,n}$ is mode shape amplitude




Figure 32: Single APS shaker random excitation force in the X-direction applied at TP1

484 at location j . $\mu_{i,n}$ is mode shape amplitude at location i . DMF is the dynamic
 485 magnification factor for steady-state harmonic response in the case of single
 486 mode, which could be given by:

$$\text{DMF} = \frac{1}{\sqrt{\left[1 - \left(\frac{hf_p}{f_n}\right)^2\right]^2 + 2\zeta_n \left(\frac{hf_p}{f_n}\right)^2}} \quad (2)$$

487 where ζ_n is the viscous damping ratio for mode n . Taking the excitation
 488 point/location as a reference (TP1), the $\mu_{j,n}$ and $\mu_{i,n}$ could assume equal 1.

489 Additionally, the structure was excited with sinusoidal input using its
 490 resonance frequencies. Due to the input energy being concentrated at a single
 491 frequency, the sinusoidal input would produce a greater acceleration response
 492 than the random white noise signal. Figure 33 shows the three-run total input
 493 force time history of the first mode resonant frequency. The corresponding
 494 structural acceleration allowance level could be calculated using equations 1
 495 and 2 and the modal parameters of the first mode, which is given by:

- 496 • The first resonant frequency: $f_1 = 2.85$ Hz,
 497 Harmonic excitation force of amplitude $P_{j,h}$ at TP1: $P_{1,1} = 770$ N,
 498 The first mode modal damping: $\zeta_1 = 1.38$ %,
 499 The first mode modal mass: $M_1 = 1067296.729$ kg, then
 500 Allowable steady-state acceleration level at TP1 of the first mode:
 501 $a_{1,1} = \frac{P_{1,1}}{M_1 \sqrt{2\zeta_1}} = 0.043$ (m/s^2)

502 The allowable acceleration level is the maximum acceptable root mean
 503 square (RMS) acceleration for a given fundamental frequency of a struc-
 504 ture. Figure 34 displays the response at TP1 related to each run. The RMS

505 acceleration value is around 0.0105 m/s^2 , which is 4 times lower than the
 506 allowable acceleration level. From this point of view, the shaker excitation
 507 is sufficient to excite the structure and ensure an adequate level of shaking,
 508 not excessively high or low.





Figure 33: Total sinusoidal input force time history using the first resonant frequency.

509 Figure 34 shows three runs' total input sinusoidal force under the second
 510 resonant mode frequency. Similarly, the modal parameters of the second
 511 mode are used to calculate the allowable acceleration level, which is given
 512 by:

- 513 • The second resonant frequency: $f_2 = 2.93 \text{ Hz}$,



514

Har-

515

monic excitation force of amplitude $P_{j,h}$ at TP1: $P_{1,2} = 813$ N,

516

The second mode modal damping: $\zeta_2 = 1.74$ %, The second mode

517

modal mass: $M_2 = 1524571.956$ kg, then Allowable steady-state accel-

518

eration level at TP1 of the second mode: $a_{1,2} = \frac{P_{1,2}}{M_2 \sqrt{2\zeta_2}} = 0.029$ (m/s^2)

519

This configuration setting of the APS electromagnetic dynamic shaker

520

could be customised to fit various low-frequency buildings and structures.

521

The adjustment requires adding a mass source to the shaker as a horizontal

522

reaction mass system, as shown in Figure 35. Table 1 also illustrates an

523

idea of the lowest frequency connected to the shaker's addition of mass bars

524

(each mass bar weighs 24.8 kg). The goal is to ensure the force can supply

525

sufficient excitation and full steady energy to drive the shaker. Therefore,

526

it was necessary to know the first mode resonant frequency in advance and

527

change the shaker's setup accordingly. The number of shakers could also be

528

employed to regulate the level of the total input force, ensuring that the force

529

suitably excites the structure. Figure 36 shows the extra information related

530

to a high-rise building in Norway to apply this methodology to capture the

531

structural dynamics.

532

6. Operational modal analysis of ambient vibration testing (AVT)

533

The ambient vibration testing could be conducted to capture dynamic

534

response under service load (i.e., wind-induced excitation). However, the




Figure 34: Acceleration response at TP1 under the first resonant frequency sinusoidal excitation.




Figure 35: Horizontal reaction mass system with APS shaker.

Quantity of mass bars	0	2	4	6	8	10	12	14	16	18	20	22
Lowest frequency for rated force (Hz)	1.11	0.9	0.83	0.8	0.69	0.64	0.6	0.6	0.55	0.52	0.5	0.48

Table 1: Horizontal reaction mass system extra mass versus lowest rate frequency



Figure 36: Photo of the application of APS shaker with horizontal reaction mass system.

535 amount of sway produced by wind is mostly small amplitude/movement than
536 the dynamic exciters created. Additionally, the low-frequency dynamic char-
537 acteristics have always been easily generated by the service load, whereas the
538 high-frequency dynamic characteristics are difficult to get using the OMA
539 method.

540 The x and y directional acceleration time histories of each test point
541 channel under ambient loading are shown in Figure 37. The measurement
542 duration of the ambient data was around an hour. It can be seen that wind
543 excitation caused some considerable amplitude/vibration to occur at specific
544 times, particularly around 3000, 4000, and 4500 s. The response during rest
545 time remained at the usual vibration level.

546 As illustrated in Figure 38, the acceleration raw time history data could be
547 used to obtain the power spectral density function (PSD). The low-frequency
548 dynamics could readily be captured using the peak-picking technique (e.g.,
549 under 6 Hz for Yoker Building); however, high-frequency modes could not be
550 excited by the ambient loading since there was not enough energy (e.g., over
551 10 Hz for Yoker Building). The measured result using FRF (see Figure 28)
552 demonstrated better high-frequency dynamic response capturing. Addition-
553 ally, the frequency range of roughly 6 to 8 Hz in the ambient OMA result
554 could not provide a good compromise to the FRF-based measurement.

555 The identified modes of a structure can be effectively visualised using
556 a stabilisation diagram of the covariance-driven subspace stochastic identi-
557 fication (SSI-COV) results. The stabilisation diagram provides a graphical




Figure 37: One-hour acceleration time history of ambient vibration testing in X- and Y-directions




Figure 38: Power spectral density function (PSD) of the ambient vibration testing data.

558 representation of a system's poles (modes) at different model orders when
 559 identifying the modal parameters (see Figure 15 left-hand side y-axis). The
 560 blue circle symbol represents the stable poles, which occurred between 2.5-
 561 4 Hz and 8.5-9 Hz.




Figure 39: Stabilisation diagram

562 The estimated modal characteristics of the structure under ambient excit-
 563 ation are shown in Figure 40. The environmental loading efficiently aroused
 564 the low-frequency range 2-5 Hz modes, and stability verification from Fig-
 565 ure 39 also provided assurance that these range estimated modes are logical.
 566 However, comparing the damping values estimation from output-only OMA
 567 and FRF-based measurement, the output-only result is usually higher than
 568 FRF curve-fitting. Furthermore, compared to FRF-based measurement (see
 569 Figure 28), the frequency range 6-9 Hz modes are hardly found since they
 570 could not have been significantly caused by the ambient loading (see Figure
 571 38). Additionally, the stability checking in Figure 39 is inevitably shown that
 572 6-7 Hz mode is not a reliable mode via ambient OMA.

573 Looking at the estimated modal properties, notable advantages of the
 574 FRF-based modal testing relative to the standard output-only AVT are:

- 575 (a) Ability to identify well higher modes of vibration which is practically
 576 not possible with AVT relying on environmental loading (e.g., wind),
 577 which simply does not have the energy in the 7-12 Hz region and cannot
 578 excite modes in that frequency range. AVT-based methods to estimate
 579 modal properties of as-built operational buildings almost never measure
 580 higher order bending modes of vibration of multi-storey buildings as
 581 reliably as demonstrated here.




Figure 40: Estimated modal properties using ambient vibration testing data

- 582 (b) In multi-storey timber buildings in particular, which tend to have rel-
583 atively high fundamental frequency compared with really tall standard
584 steel and/or concrete multi-storey buildings, these higher modes may
585 be useful to estimate the as-built stiffness of connection joints by FE
586 model updating. This is because the such high frequency and clean
587 bending modes engage structural joints much more than the funda-
588 mental modes of vibration. This study is beyond the scope of this
589 paper and is presented elsewhere ([8]).
- 590 (c) Damping values are notably higher in the cluster of higher modes (apart
591 from mode 7 outlier value) compared with the cluster of the lower
592 modes. It is not clear what is causing this and is speculated there that
593 it could also be a feature of the greater engagement of timber joints
594 which do not contribute only to the structural stiffness but also to its
595 damping. This feature merits further investigation.

596 7. Conclusions

597 This paper presented a novel input-output FRF-based MT of a multi-
598 storey CLT residential building with 42 occupied flats in normal operation.
599 The key observations and conclusions are listed below.

- 600 • The testing was a success, although it was carried out exceptionally fast
601 within only a single working day but following 6 months of preparations.
602 The testing lasted only 10 h from arrival to the site and starting the
603 instrumentation from scratch to leaving the site completely.
- 604 • The testing was carried out using purposely built OCXO-synchronised
605 data loggers, which did not require connecting signal wires running
606 through the building. This even though every of the six-floor levels
607 was monitored at least at four horizontal DOFs, yielding excellent de-
608 scriptions of the mode shapes over 26 DOFs throughout the whole
609 building.
- 610 • The limited common area of the building corridor leading to individual
611 flats at each level, over which the instrumentation was allowed, was suf-
612 ficient to measure key modal features of the building structure. This
613 was helped and confirmed by the key features of the pre-test FE model,
614 which correlated well with the modal data from the limited set of meas-
615 urement points.

- 616 • Random excitation 0-12 Hz by three synchronously running APS400
617 shakers with a total force of only 500 N RMS was able to excite
618 the whole 1300-tonne building sufficiently to yield good quality FRFs
619 between the excitation DOF at TP1 at the top of the building and
620 response DOFs throughout the building. Key to this was the low-noise
621 OXCO-based data acquisition system coupled with excellent ultra-sensitive
622 DC accelerometers.

- 623 • A QA process was followed throughout the testing ensuring the best
624 quality modal data for not less than eight modes of vibration. This is a
625 significant number of quality modes compared to typical AVT output-
626 only methods used on operational multi-storey buildings. Preliminary
627 FE analysis was carried out to inform the modal testing and provide
628 confidence in the measured FRF and modal data during the intense
629 10h of field testing.

- 630 • In the low-frequency region of the measured FRFs a useful feature has
631 been the ability to estimate experimentally the horizontal static stiff-
632 ness at the top of the building, a feature not seen before for tall struc-
633 tures. It was shown that the preliminary best practice FE model was
634 over-predicting the static stiffness by only up to 22 % of the measured
635 values.

- 636 • In the high-frequency region of the measured FRFs higher order modes
637 of vibration were identified in the region 7-12 Hz yielding in general
638 modal damping ratios of over 3 %. This damping ratio is quite high
639 for a multi-storey building. These high-order mode shapes could fur-
640 ther be used to investigate sources of stiffness and damping in timber
641 joints in a manner not done before. This is because such higher modes
642 of vibration of a timber building have not been experimentally meas-
643 ured in the past in the 7-12 Hz region, which is quite typical for novel
644 multi-storey CLT buildings. Although beyond the scope of this paper,
645 this could be a consequence of the higher modes bending more and
646 engaging more the CLT connections than the lower-order modes. This
647 greater engagement, in turn, generates more modal damping in the
648 higher-order modes. This is an important feature that needs further
649 investigation and could be exploited in new designs of CLT structures.

650 8. Acknowledgement

651 The support of ERA-NET Cofund Forest Value (for the DynaTTB project
652 <https://www.dynattb.com>) and the corresponding funding bodies (Ministry
653 of Education, Science and Sport of the Republic of Slovenia and UK Forestry
654 Commission). Special thanks go to Smith and Wallwork Ltd at Cambridge,
655 UK who are designers of the Yoker building for providing the required design
656 information and helping secure access to the structure.

657 References

- 658 [1] K. C. S. Kwok, Human perception and tolerance of wind-induced building
659 motion. Chapter 12 in *Advanced Structural Engineering*, Edited by
660 Y. Tamura and A. Kareem., Springer, 2013.
- 661 [2] A. E. Aktan, J. M. W. Brownjohn, Structural identification: Oppor-
662 tunities and challenges, *ASCE Journal of Structural Engineering* (10)
663 (2013) 1639–1647.
- 664 [3] N. Satake, K. Suda, T. Arakawa, A. Sasaki, Y. Tamura., Damping evalu-
665 ation using full-scale data of buildings in japan, *ASCE Journal of Struc-
666 tural Engineering* (4) (2003) 440–477.
- 667 [4] S.-K. Au, *Operational Modal Analysis - Modeling, Bayesian Inference,
668 Uncertainty Laws*, Springer, 2017.
- 669 [5] C. Rainieri, G. Fabbrocino, *Operational Modal Analysis of Civil Engin-
670 eering Structures*, Springer, 2014.
- 671 [6] W. K. Ao, A. Pavic, Discovering the dynamic properties of civil struc-
672 tures with frf-based and wirelessly synchronised, distributed ocxo high-
673 precision data loggers, In: *IMAC-XXXIX Congress*, Orlando, FL, USA,
674 8-11 February.
- 675 [7] D. T. A. DTA, *The dynamic test agency handbook*, Tech. rep., Dynamic
676 Testing Agency-NAFEMS (1994).
- 677 [8] B. Kurent, B. Brank, W. K. Ao, Model updating of seven-storey cross
678 laminated timber building designed on frequency-response-functions-
679 based modal testing, *Structure and Infrastructure Engineering* (1).

- 680 [9] Stora Enso, European technical assesment ETA-14/0349 of 03.06.2019,
681 Tech. rep., Austrian institute of construction engineering (2019).
- 682 [10] J. M. W. Brownjohn, S.-K. Au, Y. Zhu, Z. Sun, B. Li, J. Bassitt, E. Hud-
683 son, H. Sun, Bayesian operational modal analysis of jiangyin yangtze
684 river bridge, *Mechanical Systems and Signal Processing* (1).
- 685 [11] W. K. Ao, A. Pavic, Frf-based modal testing of horizontally swaying
686 structures using oexo synchronized wireless accelerometers for simultan-
687 eous force and vibration responses measurements, In: *EURODYN 2020*
688 *XI International Conference on Structural Dynamics*, Athens, Greece,
689 23-25 November.
- 690 [12] Honeywell International, Inc., Q-flex qa-750 accelerometer, Tech. rep.,
691 Honeywell International, Inc. Defense and Space Electronic Systems
692 Redmond (2020).
- 693 [13] Japan Aviation Electronics Industry, Ltd., Mems ja-70sa accelerometers,
694 Tech. rep., Japan Aviation Electronics Industry, Ltd. (2021).
- 695 [14] D. Ewins, *Modal Testing Theory and Practice*, Research Studies Press
696 LTD, 1984.
- 697 [15] V. T. Inc, ME'SCOPE, Vibrant Technology Inc.: www.vibetech.com,
698 March 2020.
- 699 [16] Report of a Concrete Society Working Party, Tr 43 post-tensioned con-
700 crete floors - design handbook 2nd edition, Tech. rep., Japan Aviation
701 Electronics Industry, Ltd. (2005).